

CALL FOR QUOTATION FOR CONSTR OF MAIN GATE AT APS BATHINDA

1. Quotations are being asked for constr of Main Gate at APS Bathinda as per description given below :-

S No	Details of Work	A/U	Qty
(a)	Iron Gate Double door gate made from Drought Iron of 10 Feet (Height) x 18 Feet (Width) with Iron Grills of 1 Inch thickness embedded and separated by 3 Inch each. Sides/edge grills of thickness 2.5 Inch with provision of hinges (Minimum two each side) for fixing with pillars with rollers at bottom. (Diagram of Main gate is attached along with).	Job	01
(b)	Pillars. 02 x Main Pillars of 14 feet x 3.5 feet x 3.5 feet (Height x width x depth), constructed with reinforced cement concrete mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator. Steel mesh of size 6 inch x 6 inch of thickness 8mm to 10mm with plastering. 02 x Side Pillars of 10 feet x 3.5 feet x 3.5 feet, constructed with reinforced cement concrete mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator. Steel mesh of size 6 inch x 6 inch of thickness 8mm to 10mm with plastering. Lighting. Installation of 04 x LED Lights (Warm white) with electrical fitting.	Job	01
(c)	Beams . Beam 26 feet x 3 feet x 1.5 feet (L x H x D) with brick work and plastering. Upper base side brick work. 115mm thick brick wall in cement and sand mortar 1:5	Job	01
(d)	Triangular Top. Triangular top of 18 feet x 2 feet (L x H) with brick work and plastering 115mm thick brick wall in cement and sand mortar 1:5	Job	01
(e)	Granite Work . Black Granite Stone tiles 15mm to 20mm thick in skirting, for main pillars, side pillars, beam and triangular top, laid in 12.5mm thick cement mortar 1:3 and jointed with cement slurry mixed with pigment to match the shade of stone, including rubbing and polishing labour for fixing dowel pins and cramps.	Sq Feet	900
(f)	Steel letter of size 15" per letter to be pasted on the Beam (ARMY PUBLIC SCHOOL BATHINDA) and with two side logo (Logos soft copy will be provided by school).	Nos	24

2. **Terms & Conditions:-**

- (a) Interested vendors are requested to visit the school during working hours to assess the scope of civil work between **25 Sep 2024 to 27 Sep 2024**. Please contact the undersigned for details on the quantum of work required. For scheduling a visit or inquiries, kindly call 76260-04733.
- (b) Quotations must include all information, including pricing, delivery terms, and any relevant certifications.
- (c) All prices must be quoted in (Indian rupees) and must be inclusive of all applicable taxes, duties, and charges. Installation/Labour charges to be included in the quotation only.
- (d) **The duration of completion of work is 10 days after placing the Supply Order. Delayed completion may result in penalties or cancellation of the contract.**
- (e) You are requested to forward the quotation by Regd Post/E-mail by **27 Sep 2024**. Quotations submitted after the deadline will not be considered. E-mail address of APS Bathinda is apsbathindacantt@gmail.com
- (f) Please ensure that "**CALL FOR QUOTATION FOR CONSTR OF MAIN GATE AT APS SCHOOL**" be mentioned on the outside of the sealed envelope.

Complete payment will be made after completion of work through cheque only. No advance payment will be made.



Yours Sincerely,

Garima

(Mrs Garima Sharma)
Offg Principal

